



BOYA 44 A BOYA 45							
VOLUMEN DE SEDIMENTOS NOVIEMBRE Y DICIEMBRE 2010							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO PARCIAL (m ³)	VOLUMEN DRAGADO ACUMULADO (m ³)	
			PARCIAL	PROMEDIO			
VOLUMEN DE MATERIAL SEDIMENTADO TRAMO: (54+600 - 56+700)							
44	54+600		281.40	281.40			
		100.00			294.38	29,438.00	
	54+700		307.36	307.36			
		100.00			312.23	31,222.50	
	54+800		317.09	317.09			
		100.00			316.34	31,634.00	
	54+900		315.59	315.59			
		100.00			323.02	32,302.00	
	55+000		330.45	330.45			
		100.00			334.24	33,423.50	
	55+100		338.02	338.02			
		100.00			314.11	31,410.50	
	55+200		290.19	290.19			
		100.00			300.66	30,065.50	
	55+300		311.12	311.12			
		100.00			309.26	30,925.50	
	55+400		307.39	307.39			
		50.00			309.61	15,480.25	
	55+450		311.82	311.82			
		50.00			315.53	15,776.50	
	55+500		319.24	319.24			
		50.00			300.57	15,028.50	
	55+550		281.90	281.90			
		50.00			266.78	13,338.75	
	55+600		251.65	251.65			
		50.00			260.35	13,017.25	
	55+650		269.04	269.04			
		50.00			253.14	12,656.75	
	55+700		237.23	237.23			
		50.00			239.97	11,998.50	
	55+750		242.71	242.71			
		50.00			231.84	11,591.75	
	55+800		220.96	220.96			
		50.00			210.79	10,539.25	
	55+850		200.61	200.61			
		50.00			199.74	9,987.00	
	55+900		198.87	198.87			
		50.00			211.71	10,585.25	
	55+950		224.54	224.54			
		50.00			206.53	10,326.25	
	56+000		188.51	188.51			
		50.00			189.29	9,464.25	
	56+050		190.06	190.06			
		50.00			177.21	8,860.50	
	56+100		164.36	164.36			
		50.00			166.36	8,318.00	
	56+150		168.36	168.36			
		50.00			161.98	8,099.00	
	56+200		155.60	155.60			
		50.00			140.97	7,048.25	
	56+250		126.33	126.33			
		50.00			131.80	6,590.00	
	56+300		137.27	137.27			
		50.00			127.15	6,357.50	



BOYA 44 A BOYA 45							
VOLUMEN DE SEDIMENTOS NOVIEMBRE Y DICIEMBRE 2010							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO	VOLUMEN DRAGADO	
			PARCIAL	PROMEDIO	PARCIAL (m ³)	ACUMULADO (m ³)	
VOLUMEN DE MATERIAL SEDIMENTADO TRAMO: (54+600 - 56+700)							
	56+350		117.03	117.03			
		50.00			98.60	4,930.00	460,415.00
	56+400		80.17	80.17			
		50.00			77.44	3,872.00	464,287.00
	56+450		74.71	74.71			
		50.00			87.53	4,376.50	468,663.50
	56+500		100.35	100.35			
		50.00			74.21	3,710.25	472,373.75
	56+550		48.06	48.06			
		50.00			40.11	2,005.25	474,379.00
	56+600		32.15	32.15			
		50.00			27.31	1,365.50	475,744.50
	56+650		22.47	22.47			
		50.00			20.50	1,024.75	476,769.25
45	56+700		18.52	18.52			
VOLUMEN DE MATERIAL SEDIMENTADO BOYA 44 - 45							476,769.25 m³

N CALCULADO	476,769.25 m³
MENOS VOL. OCT. ANEXO 5	104,947.45 m ³
Diferencia Nov. - Diciembre	371,821.80 m ³
Vol. Nov. Y Dic. /2	185,910.90 m³