



CALCULO DE RESEDIMENTACION - MES DE SEPTIEMBRE Y OCTUBRE							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO PARCIAL (m ³)	VOLUMEN DRAGADO ACUMULADO (m ³)	
			PARCIAL	PROMEDIO			
VOLUMEN DE MATERIAL RESEDIMENTADO TRAMO: (54+450 - 56+200)							
	54+450		625.22	62.52			
		50.00			57.23	2,861.64	
	54+500		519.43	51.94			
		50.00			52.09	2,604.29	
	54+550		522.28	52.23			
		50.00			60.40	3,019.86	
	54+600		685.66	68.57			
		50.00			79.10	3,954.81	
	54+650		896.26	89.63			
		50.00			88.86	4,443.06	
	54+700		880.97	88.10			
		50.00			83.71	4,185.70	
	54+750		793.31	79.33			
		50.00			79.89	3,994.40	
	54+800		804.45	80.44			
		50.00			76.05	3,802.45	
	54+850		716.54	71.65			
		50.00			83.17	4,158.48	
	54+900		946.85	94.69			
		50.00			93.08	4,653.80	
	54+950		914.66	91.47			
		50.00			115.43	5,771.40	
	55+000		1,393.90	139.39			
		50.00			113.04	5,652.14	
	55+050		866.96	86.70			
		50.00			89.71	4,485.54	
	55+100		927.26	92.73			
		50.00			98.62	4,930.82	
	55+150		1,045.07	104.51			
		50.00			94.13	4,706.66	
	55+200		837.59	83.76			
		50.00			73.98	3,698.97	
	55+250		642.00	64.20			
		50.00			58.67	2,933.38	
	55+300		531.36	53.14			
		50.00			54.00	2,699.90	
	55+350		548.60	54.86			
		50.00			59.89	2,994.48	
	55+400		649.19	64.92			
		50.00			69.01	3,450.38	
	55+450		730.97	73.10			
		50.00			70.94	3,546.97	
	55+500		687.82	68.78			
		50.00			60.22	3,010.78	
	55+550		516.49	51.65			
		50.00			50.56	2,527.91	
	55+600		494.68	49.47			
		50.00			48.11	2,405.53	
	55+650		467.54	46.75			
		50.00			43.80	2,190.22	
						92,683.59	



CALCULO DE RESEDIMENTACION - MES DE SEPTIEMBRE Y OCTUBRE							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO PARCIAL (m ³)	VOLUMEN DRAGADO ACUMULADO (m ³)	
			PARCIAL	PROMEDIO			
VOLUMEN DE MATERIAL RESEDIMENTADO TRAMO: (54+450 - 56+200)							
	55+700		408.55	40.86			
		50.00			41.08	2,053.93	
	55+750		413.02	41.30			
		50.00			31.22	1,561.02	
	55+800		211.39	21.14			
		50.00			22.33	1,116.48	
	55+850		235.20	23.52			
		50.00			21.56	1,077.83	
	55+900		195.93	19.59			
		50.00			25.44	1,272.00	
	55+950		312.87	31.29			
		50.00			29.87	1,493.30	
	56+000		284.45	28.44			
		50.00			20.68	1,033.89	
	56+050		129.11	12.91			
		50.00			16.29	814.28	
	56+100		196.61	19.66			
		50.00			20.38	1,018.81	
	56+150		210.92	21.09			
		50.00			16.45	822.32	
	56+200		118.01	11.80			
VOLUMEN DE MATERIAL RESEDIMENTADO 54+450 - 55+600 SEPT. Y OCT						104,947.45 m³	