



BOYA 44 A BOYA 45							
VOLUMEN DE RESEDIMENTACION MES DE ENERO 2011							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO	VOLUMEN DRAGADO	
			PARCIAL	PROMEDIO	PARCIAL (m ³)	ACUMULADO (m ³)	
44	54+400		482.14	48.21			
		50.00			69.80	3,489.94	
	54+450		913.84	91.38			
		50.00			119.51	5,975.74	
	54+500		1,476.46	147.65			
		50.00			117.87	5,893.61	
	54+550		880.99	88.10			
		50.00			114.39	5,719.58	
	54+600		1,406.84	140.68			
		50.00			121.68	6,084.01	
	54+650		1,026.76	102.68			
		50.00			136.11	6,805.53	
	54+700		1,695.45	169.55			
		50.00			168.88	8,443.89	
	54+750		1,682.10	168.21			
		50.00			172.47	8,623.48	
	54+800		1,767.29	176.73			
		50.00			179.56	8,978.25	
	54+850		1,824.01	182.40			
		50.00			180.23	9,011.37	
	54+900		1,780.54	178.05			
		50.00			184.38	9,218.97	
	54+950		1,907.05	190.70			
		50.00			197.02	9,851.18	
	55+000		2,033.42	203.34			
		50.00			204.22	10,210.81	
	55+050		2,050.90	205.09			
		50.00			200.61	10,030.74	
	55+100		1,961.40	196.14			
		50.00			193.03	9,651.25	
	55+150		1,899.11	189.91			
		50.00			186.99	9,349.34	
	55+200		1,840.63	184.06			
		50.00			177.58	8,879.16	
	55+250		1,711.03	171.10			
		50.00			164.72	8,236.07	
	55+300		1,583.39	158.34			
		50.00			157.56	7,878.23	
	55+350		1,567.90	156.79			
		50.00			160.07	8,003.50	
	55+400		1,633.50	163.35			
		50.00			162.62	8,131.20	
	55+450		1,618.98	161.90			
		50.00			158.54	7,926.81	
	55+500		1,551.74	155.17			
		50.00			147.92	7,395.99	
	55+550		1,406.65	140.67			
		50.00			132.74	6,636.99	
	55+600		1,248.14	124.81			
		50.00			124.21	6,210.29	
						196,635.95	



BOYA 44 A BOYA 45							
VOLUMEN DE RESEDIMENTACION MES DE ENERO 2011							
# DE BOYA	ESTACION	LONGITUD	AREA (m ²)		VOLUMEN DRAGADO	VOLUMEN DRAGADO	
			PARCIAL	PROMEDIO	PARCIAL (m ³)	ACUMULADO (m ³)	
	55+650		1,235.97	123.60			
		50.00			118.47	5,923.71	202,559.65
	55+700		1,133.51	113.35			
		50.00			103.46	5,173.02	207,732.68
	55+750		935.70	93.57			
		50.00			86.30	4,315.04	212,047.72
	55+800		790.32	79.03			
		50.00			73.63	3,681.60	215,729.32
	55+850		682.33	68.23			
		50.00			71.57	3,578.72	219,308.04
	55+900		749.16	74.92			
		50.00			70.55	3,527.34	222,835.39
	55+950		661.77	66.18			
		50.00			58.40	2,919.76	225,755.15
	56+000		506.13	50.61			
		50.00			48.53	2,426.62	228,181.78
	56+050		464.52	46.45			
		50.00			48.83	2,441.27	230,623.04
	56+100		511.99	51.20			
		50.00			48.99	2,449.32	233,072.36
	56+150		467.74	46.77			
		50.00			41.61	2,080.60	235,152.96
	56+200		364.50	36.45			
		50.00			31.79	1,589.46	236,742.42
	56+250		271.28	27.13			
		50.00			22.21	1,110.65	237,853.08
	56+300		172.98	17.30			
		50.00			12.77	638.36	238,491.44
	56+350		82.37	8.24			
		50.00			9.11	455.59	238,947.03
	56+400		99.87	9.99			
		50.00			8.51	425.34	239,372.37
	56+450		70.26	7.03			
		50.00			6.05	302.73	239,675.09
45	56+500		50.83	5.08			
VOLUMEN DE MATERIAL RESEDIMENTADO BOYAS 44 - 45							239,675.09 m³